



## SCOPE OF WORK

VariBlast were contracted to carry out works to remove existing paint from 2100m<sup>2</sup> of the South and West facing facades of Kensington Olympia.

The paint was removed by first applying Tensid Tavec 201 paint stripper and then pressure washing using the high temperature DOFF system.

Following the paint removal, all areas were cleaned with a cold-water pressure system to ensure the complete removal of all other traces of dirt and grime.

PROJECT NAME	Kensington Olympia
LOCATION	London
CLIENT	Kensington Olympia
PRINCIPAL CONTRACTOR	Cemplas Ltd
DURATION	8 Weeks
COMPLETION DATE	June 2012
SERVICES USED	DOFF System
MATERIALS USED	Tensid

